

Overhead 3 Phase Electric Line Construction Scope of Work

There will be one road crossing CR 532 West
City of Bushnell has all permits in hand
At the north end of project there will be one Railroad crossing going East, Setting 2 - 50ft.
concrete poles 5,000 lbs. MOL
Other poles are 45-2 wood (55)
225 ft. spans
336 MCM primary, 2/0 ACSR neutral
2 dead ends with double anchors
2 horizontal poles at CR 532 West
Should be able to do three pulls, using temporary anchors
Poles will be set 20' MOL from edge of road
MOT will be provided by City of Bushnell
City has a show up for Contractor
A few poles may need air compressor (wet area) 1,000 ft.
City has rollers and puller available at present time
Pole locations and locates provided by City
This is a design/build project, meaning at the present time no staking sheets are available
Please provide price and time frame to complete

ALTERNATE 1

May have 1.7 miles three phase 1\0, with #2 neutral across pasture to build, 45-2 wood poles ,
225 ft. span average, it is still in design